

4

3


2

1




REVISION HISTORY			
REV	DESCRIPTION	DATE	APPROVED
A	RELEASE FOR PILOT [C26489]	30NAR20	FXG



- NOTES: UNLESS OTHERWISE SPECIFIED
1. INTERPRET DRAWING PER ANSI/ASME Y14.5
 2. MATERIAL: SEE COMPONENT PRINTS
 3. FINISH: SEE COMPONENT PRINTS
PARTS SHALL BE CLEAN AND FREE OF FOREIGN MATTER.
ALL DIMENSIONS APPLY AFTER PLATING.
 4. ALL MATERIALS SHALL BE ROHS COMPLIANT.
 5. PARTS SHALL BE PACKAGED TO PREVENT DAMAGE IN SHIPMENT AND HANDLING.
 6. VSWR TEST SPEC:
MEASURED WITH 17 FEET OF CABLE:
2.4~2.5GHz < 2.0:1
4.9~5.9GHz < 2.0:1




PLASTIC RADOME UV STABLE
COLOR: BLACK



HARDWARE DETAIL VIEW

QMA CONNECTOR MEASUREMENT GAUGE FOR
THE CENTER PIN DEPTH: 1.5mm MIN ~1.7mm MAX

SUPPLIER PRINT ACCEPTANCE: [] Accept drawing/specification: No changes needed: [] This part is RoHS compliant [] This part is REACH compliant [] Accept drawing/specification. Notes/Mark-ups added [] Cannot accept drawing/spec. Notes/Mark-ups added Supplier Projected Outgoing Quality: SIGMA LEVEL : _____or PPM: _____ Signature: _____Date: _____	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN MILLIMETERS	PART WEIGHT:	DRAWN	DATE	 PCTEL, INC. ANTENNA PRODUCTS 471 BRIGHTON DRIVE BLOOMINGDALE, IL 60108 PH. 630-372-6800 FAX. 630-372-8077	
	FOR TOLERANCES NOT SPECIFIED USE: [X mm ± 3 mm], [X.X mm ± .3 mm] [X.XX mm ± .13 mm], ANGULAR± 1°	N/A	FXG	3/30/2020		
	THIRD ANGLE PROJECTION	MATERIAL:	CHECKED	DATE		
		SEE COMPONENT PRINTS				
	PROPRIETARY DATA	FINISH:	DRAWING NO.		SHEET	
THE INFORMATION CONTAINED IN THIS DOCUMENT IS OF A PROPRIETARY NATURE AND MAY NOT BE USED OR REPRODUCED WITHOUT THE EXPRESSED WRITTEN PERMISSION OF PCTEL INC., BLOOMINGDALE, IL 60108	SEE COMPONENT PRINTS	TRPS-20INT-2458B				
			SIZE	B	SCALE	1:1